3D laser scanning, as-built models and the engineering that follows

We scan the hull or structure, build the as-built 3D model, and run the structural and stability work on that same model. All in one small firm in Newport, RI.

UEI	CAGE	BUSINESS TYPE	NAICS
NWJRCE69AWH9	26AB1	U.S. small business Since 2018	541330 · 541370 · 541380 · 541690 · 541715

What we do

- **3D laser scanning.** Hulls, decks, appendages and structure, scanned with our own FARO scanner.
- **As-built 3D models.** Surface models and drawings in Rhino and SolidWorks, ready for engineering, repair or new parts.
- **Structural analysis on the scan.** FEA on the as-built geometry in Femap/Nastran and SolidWorks Simulation.
- **Stability and USCG compliance.** Hydrostatics and stability in GHS and Orca3D. Inclining tests. Stability and rig-loads reports for the USCG (46 CFR Subchapter T).
- **Deliverables.** Registered point cloud (E57 and native FARO), FARO SCENE registration report, measurement report, as-built model (Rhino, SolidWorks or STEP; Rhino opens directly in Orca3D), DWG drawings, and an engineering report when analysis is ordered.

Why Wyspa

- Scan, model and analysis in one firm. No hand-off between a scan vendor and an engineering firm.
- Naval architects run the scan, so the model comes back ready for engineering.
- We come to the vessel. On a recent repair-yard job, we handled the access forms and insurance certificate.

101 of 191

projects where scanning fed the engineering

Track record (commercial)

- **85 ft aluminum patrol boat** (2026). Scanned on site in a working repair yard. As-built 3D model of the outer surfaces in progress.
- **USCG Subchapter T conversions.** A historic 12 Metre (USCG approved) and a 12-passenger Pearson 35 (structure approved, rig review pending). Scans on both; inclining test, stability and rig-loads reports on the Pearson.
- Other scans: a 114 ft motor yacht, an aircraft fuselage and wings, keels, rudders and rigs.

How to order

- **Files by your date.** We plan the job around the delivery date in your RFQ.
- **Fixed price.** We quote a fixed price for small purchase orders. Each quote names the scanner and the accuracy of the files we deliver. Send RFQs to casey@wyspa.tech.

Casey Brown, Owner & Naval Architect
Wyspa Technologies LLC
B.S. Naval Architecture & Marine Engineering, Webb Institute (2016)

casey@wyspa.tech · (401) 523-4920
79 Thames St, Newport, RI 02840
gov.wyspa.tech